

DEBOARD REPORT on the

Hakskov Skibsvaerft Nos 51 + 52

$$\text{Mld. dims} \left\{ \begin{array}{l} 70.42^m \times 10.9^m \times 6.1^m \\ = 231.0' \times 35.76' \times 20.02' \end{array} \right.$$


$$\text{Moulded draught desired (revised)} = 15'-9"$$

- (1) The equivalent moulded depth of a full scantling flush deck ship, with 50% excess sheer to give a moulded draught of 15'-9" for all seasons = 18'-11 1/2"

- (2) The equivalent moulded depth of a full scantling ship with actual erections (45.6% covered), and 50% excess sheer, to give a moulded draught of 15'-9" for all seasons = 18'-2 1/2"

Copy to Mr Potts

009232 - 009234 - 0034



© 2020

Lloyd's Register
Foundation

27.7.31