

Lloyd's Register of Shipping.

Ship's Name **SAN VALERIO.**Official No. **135301.**

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Hatchways on Freeboard & Superstructure Decks.

* The small hatch on upper Deck fore to Auxly Pump Room now fitted with w/t steel cover with wing nuts & bolts.

An access manhole P+S on upper deck fore to Fore c/dam 12"x19"x5" coaming with bolted steel plate cover.

The combined hatch coaming on Poop Deck Stairs to OF Bunker & Poop Tween decks has now been reduced to 12" to suit Galing at Sea (was Emergency).

A hatch has now been fitted on Poop Deck, Port, access to Refrig chamber,

30" x 30" x 5" coaming with w/t steel plate cover secured by wing bolts & bolts.

A new hatch to transome plate has now been fitted on Poop Deck. 20" x 20" x 5" coamy with w/t cover and wing nuts & bolts.

The hatch on Poop Dk P+S (aft) to Tween Decks has now been dispensed with.

COMPANIONWAYS.

Stokehold Pump Room Entrance on Poop Deck Stairs now dispensed with

A new companionway to the Poop Tween Deck Accom^{mt} has now been fitted

on Poop Dk Stairs. 4'9" x 3'0" x 6'0" high x 32. with strong wood door capable of being opened from both sides. 18" sill.

Access has now been fitted to the Greenhouse Quarters in Poop Tween Dks

Fore by a strong wood door fitted in Poop Deck casing Port. 19" Sill.

PARTICULARS OF VENTS. (LIST OF ORIGINAL & NEW).FORECASTLE.

3 @ 12" dia x 36" x .35 Coaming.
3 @ 9" " x 37" x .32 "
10 @ 6" " x 36" x .30 "
2 @ 6" " 6" to Lf. (G.N).

FOR^d WELL. UPPER DK.

1 @ 12" dia x 36" x Coaming
PUMP ROOM TOP. UPPER DK AFT.
2 @ 12" dia x 30" x Coaming

POOP DK.

1 @ 16" dia x 30" x 3/8 Coaming.
2 @ 12" " x 30" x .35 "
3 @ 9" " x 30" x .32 "
7 @ 6" " x 36" x .30 "

BRIDGE DK.

13 @ 6" dia x 30" x .30 Coaming.
2 @ 10" " x 30" x .32 Coaming.
3 @ 3" dia 21" to Lf. (G.N).

All vents fitted with wood plugs & canvas covers for closing appliances.

AIR PIPES. (LIST OF ORIGINAL & NEW).FORECASTLE DK.

1 @ 2 1/2" dia x 24" to Lf. Fore Peak.
2 @ 3 1/2" " x 10" to Lf. Fore Deck.

UPPER DK.

1 @ 4" dia 15" to Lf. Fore c/dam.
2 @ 2" " 20" to Lf. Fore c/dam.
2 @ 3" dia 70" to Lf. Aft c/dam.

POOP DK.

2 @ 3" dia 12" to Lf. OF Bunker
2 @ 2 1/2" " 30" to Lf. E.R.D.B.TK.
2 @ 2 1/2" " 30" to Lf. Aft Peak.

All Air Pipes supplied with wood plugs or Gauges.

SANITARY DISCHARGES. (LIST OF ORIGINAL & NEW)

UPPER DK. SCUPPERS. 3 fore well & 5 aft well P+S. 4" x 3" through deck.

FORECASTLE 2 WC & 2 WB Wastes (P+S) discharging 3'0" below Freeboard Dk.

1 WC & 1 WB waste Stairs
AMIDSHIPS. 2 WC & 2 WB Wastes Port } discharging 3'0" below Freeboard Dk.

1 WC, 1 WB, 1 Refrig waste Port }
POOP. 1 WB waste Stairs } discharging 3'0" below Freeboard Dk.
3 WC & 2 WB waste Stairs } discharging above Freeboard Dk.

All discharges fitted with storm valves.

A.T.O. 944.

SAN VALERIO.

SIDESCUTTLES.

The following additional sidescuttles have now been fitted,

<u>Forecastle</u>	9' dia	1 Port & 2 STAR.	} all of substantial construction with hinged deadlights
<u>AMIDSHIPS</u>	16" "	1 STAR.	
<u>Poof.</u>	16" "	2 Port.	

PARTICULARS OF FREEING ARR.

The steel bulwarks in the 74 A wells. upper deck. have now been dispensed with & Guard rails & stanchions fitted.

PARTICULARS OF CHORING APPLIANCES.

The following modifications have now been effected.

FORECASTLE FRONT. Steel hinged doors removed and strong wood doors capable of being opened from both sides fitted.

Poof Front Hinged steel doors removed and openings plated over.

STOKERHOLD PUMP ROOM ENTRANCE now removed and opening plated over.

J. J. Young.

Newcastle. 25.5.43.