

(LLOYDS REGISTER). G.R.130
VESSELS OF 100 TONS AND UPWARDS.

Form No. 19

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

Signal Letters (if any) K.L.G.N.

Official Number. 145,903.		Name of Ship. Montcalm		No., Date, and Port of Registry. 145 1921 Liverpool	
No., Date, and Port of previous Registry (if any)		New Vessel			
Whether British or Foreign Built. British	Whether a Sailing or Steam Ship; and if a Steam Ship, how propelled. Steamship Twin Screw	Where Built. Clydebank	When Built. 1921	Name and Address of Builders. Messrs. John Brown & Co. Ld. Clydebank.	
Number of Decks ...	Three	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...		549	5.0
Number of Masts ...	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...		567	2.5
Rigged ...	Fore and Aft	Main breadth to outside of plank ...		70	2.5
Stern ...	Cruiser	Depth in hold from tonnage deck to ceiling at midships ...		30	2.0
Build ...	Out and In	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...		40	2.0
Galleries ...	None	Depth from top of beam amidships to top of keel ...		44	5.0
Head ...	Straight	Depth from top of deck at side amidships to bottom of keel ...		43	6.0
Framework and description of vessel ...	(Steel Passenger & Cargo Vessel)	Round of beam ...		1	2.5
Number of Bulkheads ...	Twelve	Length of engine room (if any) ...		167	4.0
Number of water ballast tanks, and their capacity in tons ...	Thirteen 1171 Tons Total				

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel **26235** Tons. Ditto per inch immersion at same depth } **78.2** Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	B. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.	No. of Cylinders in each set.	
Two	Double Reduction Geared Turbines	Engines. British	Engines. 1921	Engines. Messrs. John Brown & Co. Ltd. Clydebank	---	---	Three	11500
Two	Cylindrical tubular Marine Steel Boilers	do	do	do				16 Knots
	215 lbs.							

PARTICULARS OF TONNAGE.

GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...		9093.89	On account of space required for propelling power...	5253.76
Space or spaces between Decks ...	12155.95	3062.06	On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from Goods or Stores of every kind, not being the personal property of the Crew ...	1118.57
Turret or Trunk ...		1874.55	These spaces are the following, viz:—	
Forecastle ...		1562.30	Forecastle, Round Houses, and Upper Bridge.	
Bridge space ...		825.20	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Poop or Break ...			Tons	
Side Houses ...			Master 28.85	
Deck Houses ...			Boatswain's Stores 57.65	
Chart House ...			Wireless House 6.19	
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894,			Chart Space 12.64	256.22
Excess of Hatchways ...			Steam Steering House 50.13	
			Water Ballast Spaces 100.76	
Gross Tonnage ...		16418.00	Total ...	6628.57
Deductions, as per Contra ...		6628.55		
Registered Tonnage ...		9789.45		

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is **2286.09** tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is **372.34** tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage:

After end of Upper Bridge 1.51.7 -- 181.46 Tons.

Name of Master.

Certificate of { Service No.
Competency No.

Names, Residence and Description of the Owners, and } viz.,
Number of Sixty-fourth Shares held by each ... }

Canadian Pacific Railway Company
Montreal, Canada.
Sixty-four Shares.

Sir George McLaren Brown K.B.E.
62-65 Charing Cross
London, S.W.1.
Manager.

Dated **9th December 1921.**

Registrar

