

s.s. "CONCHITA"

This ship was built in 1920-6 by Messrs. J. Fullerton & Co., at Paisley and classed #100A1.

A Special Survey became due in 6,61 but not held and in August last the Committee gave instructions for the notation "Class With-drawn 8,62" to be recorded in the Register Book.

At this time the class was subject to the rudder and sternframe being specially examined and dealt with as necessary at the next drydocking.

In a cable dated 22.2.63 the Madrid Surveyors request the requirements for Reclassification.

IT IS THEREFORE SUBMITTED the Surveyors be advised that for Reclassification it will be necessary for:-

1. The requirements of a SPECIAL SURVEY (C) to be complied with including the drilling of the structure in such parts where signs of wastage are evident.
2. Any major repairs which have been or are to be effected to the structure since the ship was disclassed to be specially examined in order to ascertain the character of the workmanship and confirm that the materials used are in accordance with the Rules.
3. Structural alterations affecting the longitudinal and/or transverse strength of the ship which may be required at this time should be carried out in accordance with plans to be previously approved.
4. Structural alterations which may have been carried out since the ship was disclassed to be specially examined in order to ascertain the character of the workmanship and confirm that all, including materials, conform to Rule requirements, and
5. full particulars of the equipment on board, including weights, tests and condition of anchors, also length, diameter, tests and condition etc. of chain cable to be furnished for consideration.

A complete E.S. M.B.S., T.S. and
S.P.S. to be carried out.

22.2.63.

22.2.63

272-195600-55100