

COPY.

Lloyd's Register of Shipping,

71, Fenchurch Street, E.C. 3.

26th February, 1919.

Dear Sirs,

E. With reference to your First Entry Machinery Report No. 5321 in the case of the S.S. "GLORIA", I have to inform you as regards your remarks respecting the Condenser that provided the Condenser be tested by hydraulic pressure to 20 lbs per square inch and found to be tight and sound at that pressure it will be accepted in this instance, but if it fails to satisfactorily stand the test it will require to be fitted with 2 outside stiffeners spaced about 20 inches apart. To effect such a repair it would be necessary to remove one of the tube plates and all the tubes in order to rivet these angle stiffeners to the shell plating.

I am, Dear Sirs,

Yours faithfully,

Secretary.

The Surveyors,

BILBAO.

To await reply

Red.

27/2/19



© 2021

Lloyd's Register
Foundation

009570-009579-0052