

Engines intended for
Messrs Sdad Ano Astilleros Riera - of Gijón.
Vessel No 2 - "GLORIA".

These engines were constructed at Barcelona & were originally intended for an electric lighting installation at Salamanca.


The Bilbao Surveyors now report that Messrs Sdad Ano Astilleros Riera now propose to fit the engines into their Vessel No 2 "GLORIA," together with the necessary shafting etc.

It is submitted that with cylinders 375 x 650 mm dia, by 395 mm stroke, working pressure 130 lbs the diameter of crank shaft, and the proposed diameters of thrust & screw shafts, viz, 160, 170 & 154 mm, respectively merit approval provided the diameter of propeller does not exceed 2130 mm;

Also the plans of cylinders & condenser merit approval provided the thickness of 10.5 condenser shell plating be not less than 9.5 mm; such parts of the machinery as have not been constructed under the supervision of the surveyors should be opened out & examined, and on completion a report on Rpt 4 should be forwarded.

Retain - 6 plans
Return - 12 plans

Ln: - 22/12/18



JLM

21/12/18 JLP

© 2021

Lloyd's Register
Foundation

009570 - 009579 - 0056