

G.R. 130.

CLASS CONTEMPLATED

(LLOYD'S REGISTER.)

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.

Signal Letters (if any) G.L.N.D.



Official Number.	Name of Ship.	No., Date, and Port of Registry.
180563	FIREBEAM	86 in 1945 London

No., Date, and Port of previous Registry (if any).

Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Ship Single Screw	Aberdeen	1945	Hall Russell & Co. Limited, Aberdeen.

			Feet.	Tenths.
Number of Decks One	Length from fore part of stem, to the aft side of the head of the stern post	247	-	
Number of Masts Two	Main breadth to outside of <u>plank plating</u>	39	6	
Rigged Not	Depth in hold from tonnage deck to ceiling amidships ...	16	6	
Stem Straight Raking	Depth in hold from upper deck to ceiling amidships, in the case of three decks and upwards	22	6.9	
Stern Cruiser	Depth from top of deck at side amidships to bottom of keel...	-	8	
Build Clinker	Round of beam	47	2.5	
Framework and description of Steel vessel Cargo	Length of engine room, if any			
Number of Bulkheads Four Watertight				

Particulars of propelling Engines, etc. (if any), and Water Ballast Tanks, as supplied by Builders, Owners, or Engine Makers.

No. of sets of Engines	Description of Engines	Whether British or Foreign Made	When made	Name and address of makers	Reciprocating Engines		Rotary Engines	N.H.P. B.H.P. I.H.P. Estimated Speed of Ship
					No. and Diameter of Cylinders in each set	Length of Stroke		
One	Triple Expansion, Direct Acting Vertical	Engines British	Engines 1945	Engines David Rowan & Co. Ltd.,	Three 16 1/2"	33"	/	185
One	Particulars of Boilers Single Ended Multitubular Description One Number Steel Iron or Steel Loaded Pressure 200 lbs.	Boilers British	Boilers 1945	Boilers Glasgow.	27 1/2" 46"			900 10 knots

Number of water ballast tanks, and their capacity in tons:— Seven = 828 tons.

009839-009847-0148

009839-009847-0147

© 2021

Lloyd's Register Foundation

[P.T.O.]

PARTICULARS OF TONNAGE.


GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	1178.51	On account of space required for propelling power	497.19
Space or spaces between Decks		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from Goods or Stores of every kind not being the personal property of the Crew.	85.10
Fore-castle Trunk	8.57	These spaces are the following, viz.:—	
Forecastle (Houses in)	3.72	Below Deck aft, in Bridge and Round Houses	
Bridge space	32.52	(Number of Seamen or Apprentices for whom accommodation is certified.....16.....).	
Fore-castle Break	202.59	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Side Houses	1.29	Cubic Meters. Master's Accommodation 5.46)	
Deck Houses	19.54	Water Ballast Spaces 73.40)	78.86
Chart House			
Spaces for Machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894	107.19		
Excess of Hatchways			
Gross Tonnage	1553.73	4397.05	
Deductions, as per contra	660.15	1871.05	
Register Tonnage	892.58	2526.00	661.15

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 206.83 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 17.33 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Forecastle - Length 25.0 ft. = 22.91 tons

Name of Master	Certificate of	Service No.	No. Competency No.
No. of Owners			
Name, Residence, and Description of Managing Owner if there are more owners than one.			
The Gas Light & Coke Company, 30, Kensington Church Street, London, W.8.			
Shares:— Sixty-four.			
Mgr: John P.S. Clarke, 4, Fenchurch Avenue, London, E.C.3.			
Dated 25th May, 1945.			



© 2021

Lloyd's Register Foundation