

31229

# Lloyd's Register of Shipping.

Ship's Name "CITY OF KHIOS". Official No. 147293

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in \_\_\_\_\_

New Provision Room in Bridge Deck Space Port Side Aft.

Access from Bridge Deck.

Opening in Bridge Deck 4'-6" x 2'-7", Doubler fitted all round aperture, of equivalent Area to Aperture. Local Fore and Afters fitted. ✓

Companionway of Strong Steel Construction fitted over opening with Entrance Door (Wood) 2" thick, 4' 0" x 2' 1" operated both sides. Steel coaming 18" high. ✓

1 Gooseneck Ventilator to Provision Room Annex fitted on Bridge Deck, 6" diameter of Strong Steel Construction and 18" high to underside of Gooseneck. ✓

Wood plug and canvas cover supplied. ✓

Engineer's Accommodation on Bridge Deck. Starboard Side.

Forward end of House removed and extended approximately 3'-6" further forward.

Starboard Side Coaling Hatch reduced Approximately 9" in length and new end coaming fitted. ✓

*Jasb. Struthers*


Surveyor to Lloyd's Register of Shipping,

MANCHESTER.

22nd July, 1953. ✓

*John*

30 JUL 1953



© 2021

Lloyd's Register Foundation