

S.S "AARDENBURG" Ex "STAHECK."

Amsterdam Report No. 16196

Classification

The plan of the boilers has been examined and the scantlings as shown thereon, with the exception of the furnaces and combustion chamber girders, meet the requirements of the Rules for a working pressure of 14 Kg/cm.²

In the case of the furnaces and girders, these have been made from material having relatively low ultimate tensile strength, as permitted by the Germanischer Lloyd Rules, and since the boilers have been examined by the Amsterdam Surveyors and found satisfactory, it is considered the boilers could be accepted for the stated working pressure of 14 Kg/cm.²

The dimensions of the screwshaft as shown on the plan of stern tube and those of the crank, intermediate and thrust shafts as stated in the above report meet the requirements of the Rules.

 4.1.47



© 2021

Lloyd's Register
Foundation

009896-009903-0114