

23 JUL 1944

Lloyd's Register of Shipping.

Ship's Name "FORT CATARAQUI".

Official No. 168356.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in _____

Additional accommodation provided for gunners in No.5 tween decks port side.

Fitted 3 - 9" dia. ports and deadlights of substantial construction.
2 - 8" dia. cowl vents complete with wood plugs and canvas covers.
1 - 24" dia. escape scuttle with 24" high coaming closed with hinged
W.T. steel cover operated from both sides.
1 - 1½" overboard washbasin discharge with screw down non-return valve
fitted at ship side operated from above the freeboard deck.

Thos. J. Roberts (July 1944)
SURVEYOR TO LLOYD'S REGISTER.

W.F.
27 JUL 1944

