

S. S. "BEN VANNOCHE" ex "GRANDYKE"

Generators: 2-15kW. and 1-30kW generators added.

FIRST SURVEY 28/12/49

LAST SURVEY 16/1/50

Electrical Installation:-

A Special Survey of the electrical equipment was carried out, Generators, Cables fittings, and main switch board examined.

The following repairs and modifications were effected at this time:- One new steam driven Generator Set added 30kW. 110 volts 275amps 500 R.P.M. M/C No 43580 manufactured by Messrs. Sunderland Forge & Eng. Co., together with change over switch panel fitted with Ammeter, and Voltmeter. New generator cables installed in accordance with rule requirements. (Test certificate of Gunther attached)

"Marconi" type Radar installation, Browns 'A' type Gyro Compass, Hailing Equipment, and Broadcast system fitted at this time.

Engine - Boiler rooms rewired, additional flood lights added, all faults on circuits attended to, and new fittings installed where necessary.

On completion of repairs and modifications, installation seen under working conditions. Generators tested for compounding governing - voltage range. all circuits megger tested and all found to be in order.

NOTE:- Radar, Gyro Compass fitted at this time

*J W Wright*SURVEYOR TO LLOYD'S REGISTER
NEWCASTLE-ON-TYNE

10 Survey. £5.0.0 Coulson Bros Ltd.

for (New Gen) £6.6.0 Ben Linn