

117 MAY 1943

11483.

Lloyd's Register of Shipping.

Ship's Name "OCEAN VISTA".

Official No. 169057

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in _____

ADDITIONAL ACCOMMODATION.

No.5 'Tween deck. 2 - 10" diameter port lights with strong hinged deadlights fitted in way of temporary accommodation on starboard side.

Temporary accommodation now fitted on port side, entrance from existing gunners accommodation through forward steel bulkhead fitted with strongly constructed hinged steel watertight door operated from both sides. 2 - 10" diameter port lights with strong hinged deadlights fitted in way, also 2 - 6" diameter ventilators on deck above, coamings 36" high, fitted with wood plugs and canvas covers.

No.4 'Tween deck. Accommodation fitted port and starboard. Entrances from two strongly constructed wood companionways with solid wood hinged doors operated from both sides. These companionways erected on top of weather deck hatch and suitable battening down arrangements provided. 2 - 9" diameter ventilators (1 port and 1 starboard) fitted on upper deck, coamings 36" high and wood plugs and canvas covers provided.

No.3 'Tween deck. Accommodation fitted on port side and hospital fitted on starboard side. Entrances from 2 strongly constructed wood companionways with solid wood hinged doors operated from both sides. These companionways erected on top of weather deck hatch and suitable battening down arrangements provided. 2 - 9" diameter ventilators (1 port and 1 starboard) fitted on upper deck, coamings 36" high and wood plugs and canvas covers provided.

* Overboard discharge from bath on starboard side fitted with storm valve at ship's side and gate valve.

* Overboard discharge from "Baltic" type W.C. on starboard side fitted with storm valve at ship's side.

* NOTE. These overboard discharges to be altered on return of vessel to U.K. in order that they be made to conform to the Load Line Rules.

COPY OF ABOVE PLACED ON BOARD.

Noted.

S.W.B.
17 MAY 1943