

Lloyd's Register of Shipping.

Ship's Name *S. S. "ZYPENBERG."*

Official No. ✓

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in _____

To provide means of escape from the crew space, an opening has been cut in the Poop front bulkhead port side.

Size of opening 39" x 25½" having sill 34" high, and 3" 1½" angle frame bolted W.T. to bulkhead. A steel rubber jointed W.T. cover plate having four toggles operated from both sides and two lifting handles has been fitted to opening. The opening is provided as a means of escape for the crew.

A copy of this report has been placed on board the vessel.

Alex. M. Jenkins
Surveyor to Lloyd's Register of Shipping
London 28TH JANUARY 1942.

Noted *SwB*
5/2/42