

Rpt. 4.

No. 5731

Rpt. 4

REPORT ON STEAM RECIPROCATING ENGINE MACHINERY.

Received at London Office 11 JAN 1943

Date of writing Report Sept. 25th 19 42 When handed in at Local Office Sept. 25th 19 42 Port of MONTREAL, QUE.

No. in Survey held at MONTREAL, QUE. Date, First Survey 6th June, 1942 Last Survey 21st July 19 42
Reg. Book. on the Steel Single Screw Steamer "Fort Thompson" (Number of Visits 31) Tons {Gross 7133.58
Net 4243.53

Built at VANCOUVER - BC By whom built BURRARD DRY DOCK COMPANY LIMITED - Yard No. 146 When built 1942

Engines made at LACHINE, MONTREAL, PQ By whom made DOMINION ENGINEERING WORKS LTD. Engine No. 42 When made 1942

Boilers made at By whom made Boiler No. When made

Registered Horse Power Owners Port belonging to

Nom. Horse Power as per Rule 504 505 Is Refrigerating Machinery fitted for cargo purposes No Is Electric Light fitted Yes

Trade for which Vessel is intended

ENGINES, &c. — Description of Engines Triple Expansion Revs. per minute 76

Dia of Cylinders 24 1/2" x 37" x 70" Length of Stroke 48 No. of Cylinders 3 No. of Cranks 3

Crank shaft, dia. of journals as per Rule 13.99" Crank pin dia. 14-1/4" Crank webs Mid. length breadth - - Thickness parallel to axis 9" & 9 1/2" L.P.
as fitted 14-1/4" Mid. length thickness - - Thickness around eye-hole 7.125
7.625

Intermediate Shafts, diameter as per Rule 13.33" Thrust shaft, diameter at collars as per Rule 13.99"
as fitted 13.5" as fitted 14.25"

Tube Shafts, diameter as per Rule - - Screw Shaft, diameter as per Rule 14.87"
as fitted - - as fitted 15.25" Is the {tube} shaft fitted with a continuous liner { Yes
as fitted - - as fitted 15.25"

Bronze Liners, thickness in way of bushes as per Rule .75" Thickness between bushes as per Rule .565"
as fitted .78125" as fitted .68" Is the after end of the liner made watertight in the
propeller boss Yes If the liner is in more than one length are the junctions made by fusion through the whole thickness of the liner Solid
If the liner does not fit tightly at the part between the bearings in the stern tube, is the space charged with a plastic material insoluble in water and non-corrosive Tight Fit -
If two liners are fitted, is the shaft lapped or protected between the liners - - Is an approved Oil Gland or other appliance fitted at the after end of the tube
shaft No If so, state type - - Length of Bearing in Stern Bush next to and supporting propeller 61"

Propeller, dia. 18'-6" Pitch 16'-0" No. of Blades 4 Material Bronze whether Moveable Solid Total Developed Surface 117 sq. ft.

Feed Pumps worked from the Main Engines, No. None Diameter - - Stroke - - Can one be overhauled while the other is at work - -

Bilge Pumps worked from the Main Engines, No. Two Diameter 4 1/2" Stroke 26" Can one be overhauled while the other is at work Yes

Feed {No. and size Pumps connected to the {No. and size
Pumps {How driven Main Bilge Line {How driven

Ballast Pumps, No. and size Lubricating Oil Pumps, including Spare Pump, No. and size

Are two independent means arranged for circulating water through the Oil Cooler Suctions, connected to both Main Bilge Pumps and Auxiliary
Bilge Pumps;—In Engine and Boiler Room

In Pump Room In Holds, &c.

Main Water Circulating Pump Direct Bilge Suctions, No. and size Independent Power Pump Direct Suctions to the Engine Room Bilges,
No. and size Are all the Bilge Suction Pipes in holds and tunnel well fitted with strum-boxes

Are the Bilge Suctions in the Machinery Space led from easily accessible mud-boxes, placed above the level of the working floor, with straight tail pipes to the bilges

Are all Sea Connections fitted direct on the skin of the ship Are they fitted with Valves or Cocks

Are they fixed sufficiently high on the ship's side to be seen without lifting the stokehold plates Are the Overboard Discharges above or below the deep water line

Are they each fitted with a Discharge Valve always accessible on the plating of the vessel Are the Blow Off Cocks fitted with a spigot and brass covering plate

What Pipes pass through the bunkers How are they protected

What pipes pass through the deep tanks Have they been tested as per Rule

Are all Pipes, Cocks, Valves, and Pumps in connection with the machinery and all boiler mountings accessible at all times

Is the arrangement of Valves and their connections such as to prevent the possibility of water passing from the sea or from water tanks into the cargo or machinery spaces, or from one
compartment to another Is the Shaft Tunnel watertight Is it fitted with a watertight door worked from

MAIN BOILERS, &c. — (Letter for record S) Total Heating Surface of Boilers 7140 Square feet

Which Boilers are fitted with Forced Draft All three - Which Boilers are fitted with Superheaters All three

No. and Description of Boilers 3 Single Ended Multitubular Working Pressure 220 lbs. per square inch

IS A REPORT ON MAIN BOILERS NOW FORWARDED? Yes

IS A DONKEY BOILER FITTED? No If so, is a report now forwarded? - -

Can the donkey boiler be used for domestic purposes only

PLANS. Are approved plans forwarded herewith for Shafting Main Boilers Auxiliary Boilers Donkey Boilers
(If not state date of approval)

Superheaters General Pumping Arrangements Oil fuel Burning Piping Arrangements

SPARE GEAR.

Has the spare gear required by the Rules been supplied

State the principal additional spare gear supplied

The foregoing is a correct description

Dominion Engineering Works Ltd.

Manufacturer.

per W. H. Van Batten



© 2021

Lloyd's Register
Foundation

009994-010003-0190

6,10,11,12,13,15,17,18,19,22,23,24,25,26,27,29,30th June, 1942, 2,3,6,7,8,9,10,11,14,15,

Dates of Survey while building

During progress of work in shops - -

During erection on board vessel - - -

16,18,20,21 July, 1942

Total No. of visits

Dates of Examination of principal parts — Cylinders 6.7.42, 19.6.42, 15.7.42 Slides 6.7.42, 19.6.42, 15.7.42 Covers 6.7.42, 19.6.42, 15.7.42
Pistons 6.7.42, 19.6.42, 15.7.42 Piston Rods 21.7.42 Connecting rods 21.7.42
Crank shaft 21.7.42 Thrust shaft 21.7.42 Intermediate shafts
Tube shaft Screw shaft Propeller
Stern tube Engine and boiler seatings Engines holding down bolts

Completion of fitting sea connections
Completion of pumping arrangements Boilers fixed Engines tried under steam
Main boiler safety valves adjusted Thickness of adjusting washers L.R. 3877
Crank shaft material O H Steel Identification Mark H.S. 21.7.42 Thrust shaft material O H Steel Identification Mark L.R. 5313 H.S. 21.7.42
Intermediate shafts, material Identification Marks Tube shaft, material Identification Mark
Screw shaft, material Identification Mark Steam Pipes, material Test pressure Date of Test
Is an installation fitted for burning oil fuel No Is the flash point of the oil to be used over 150°F.

Have the requirements of the Rules for the use of oil as fuel been complied with
Is the vessel (not being an oil tanker) fitted for carrying oil as cargo If so, have the requirements of the Rules been complied with
If the notation for Ice Strengthening is desired, state whether the requirements in this respect have been complied with
Is this machinery duplicate of a previous case Yes If so, state name of vessel S.S. "FORT TADOUSSAC" & S.S. "FORT CHAMBLAY"
General Remarks (State quality of workmanship, opinions as to class, &c.)

This ENGINE has been constructed under Special Survey in accordance with the Rules and Approved Plans. The Materials and workmanship are good. The cylinders were tested hydrostatically to 330, 110 and 30 lbs. pressure per square inch respectively, and found tight under those pressures.

This ENGINE has now been shipped to BURRARD DRY DOCK COMPANY LIMITED, VANCOUVER, BC, for installation and official trials. It is recommended for the favourable consideration of the Committee that the record of + L.M.C. (with date) be made in the Register Book in the case of this Vessel, subject to satisfactory installation and sea trials.

The amount of Entry Fee ... /£ 30.00 : When applied for.
Special ... /£ 267.00 : Oct. 22 1942
Donkey Boiler Fee ... £ : 26.10.42 - YCR.
Travelling Expenses (if any) /£ 20.00 : When received, 19

H. J. Saunders
(Engineer Surveyor to Lloyd's Register of Shipping.)

Committee's Minute

Assigned

FRI. 15 JAN 1943

See Vcr. 2.E. 5827



© 2021

Lloyd's Register Foundation