

"CANADIAN VICTOR"

This ship was built in 1945-8 at Lauzon, P.Q., by Messrs. G. R. Davie & Sons Ltd., and classed #100AL.

The Special Survey became due 5,57, was commenced at Montreal in 8,56 and subsequently advanced.

The Montreal Surveyors in a memorandum dated 26th July, 1957, and in subsequent correspondence stated that the ship was strike-bound at Halifax and this was followed by being laid up at that port.

On 1st December, 1961, in the absence of any proposal from the Owners for dealing with the outstanding surveys, the Committee gave instructions for the notation "Class Withdrawn 1,61" to be assigned.

When the class was withdrawn our records show an outstanding Condition of Class - Subject to set in shell plates B.13 & C.11 (s.s) from aft being dealt with by completion of the Special Survey, ACTION being DEFERRED for examination in dry dock after grounding. There was no S.R.L. Appendix item.

The New York Surveyors in their letter of 15th March, 1963, stated that Agents for prospective purchasers have enquired regarding the Society's requirements for Reclassification of the above ship.

IT IS THEREFORE SUBMITTED the Surveyors be advised that for Reclassification it will be necessary for -

1. The requirements of a SPECIAL SURVEY (C) to be complied with, including the drilling of the structure in such parts where signs of wastage are evident. (Refer C.205 of the Rules).
2. Any major repairs which have been or are to be effected to the structure since the ship was disclassified to be specially examined in order to ascertain the character of the workmanship and confirm that the materials used are in accordance with the Rules.
3. Structural alterations affecting the longitudinal and/or transverse strength of the ship which may be required at this time should be carried out in accordance with plans to be previously approved.
4. Structural alterations which may have been carried out since the ship was disclassified to be specially examined in order to ascertain the character of the workmanship and confirm that all, including materials, conform to Rule requirements, and.

5. full particulars of the equipment on board, including weights, tests and condition of anchors, also length, diameter, tests and condition etc. of chain cable to be furnished for consideration.

It is concluded that the New York Surveyors have obtained permission from the present Owners to discuss the requirements of Reclassification with the prospective purchasers.

Ji.
20.3.63.

Complete ES, PS, TS & SPS to be held.

in V.R.
20/3/63



© 2021

Lloyd's Register
Foundation