



Ex. Jander Bay
N.N. ATLAWILL
W. bambbean
Trader

Lloyd's Register of Shipping

20 JAN 1944
231 St. James Street West,

Montreal.

December 2nd, 1943

Reference
S.

The Secretary
LLOYD'S REGISTER OF SHIPPING
71 Fenchurch Street
London, E. C. 3 - England

Dear Sir;-

Montreal Report No. 5893 - "LANSDOWNE PARK"

In reply to the queries contained in the Classing
Letter dated the 17th September last, regarding the above Vessel,
Mr. Brown now confirms as follows;-

- (1) The spacing of the rivets in the treble rivetted
butt laps of the strake below the sheerstrake in
the wells is 3-1/8". ✓
- (2) A horizontal girder has been fitted to the after
peak bulkhead - ✓
- (3) The material used in the construction of this
Vessel has been tested as required by the Rules - ✓
- (4) The only part of the main structure which has been
electrically welded is the paravane stem piece. ✓
- (5) The length of the double bottom tank should read
270'-0". ✓
- (6) Bridge and forecastle decks - The length of bridge
deck between bulkheads is 78'-0" with 4'-0" overhang
at after end, making total length of 82'-0". ✓
- (7) The length of the forecastle deck was taken from the
forecastle front to forward perpendicular -

Copies of the Anchor Certificates are enclosed herewith.

We remain, Dear Sir,

Yours faithfully,

Al. H. H. H.
SURVEYOR

Enclosures
ARR/FC

Lloyd's Register
Foundation

010236-010245-0173

M
1.c.8

H
R-8

20 JAN 1944



© 2021

Lloyd's Register
Foundation



REGI