


GLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

For her humber

VESSELS OF 100 TONS AND UPWARDS.



These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.

Signal Letters (if any) V. D. Q. C.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
174,153	LANSDOWNE PARK	3-1943 Montreal, Que.

No., Date, and Port of Previous Registry (if any) **First Registry.**

Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Screw	Lauzon, Levis, Que.	1942.	Geo. T. Davie & Sons, Lauzon, Levis, Que.

Number of Decks	One	Length from fore part of stem, under the bowsprit, to the foremast-rigger	315	5
Number of Masts	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel	309	5
Rigged	Not	Main breadth to outside of plank	46	5
Stern	Cruiser	Depth in hold from upper deck to ceiling at midships in the case of three decks and upwards	23	-
Build	In & Out	Depth from top of beam amidships to top of keel	26	1
Galleries	None	Depth from top of deck at side amidships to bottom of keel	25	4
Head	Raked	Round of beam	-	9
Framework and description of vessel	Steel Cargo	Length of engine room, if any	44	-
Number of Bulkheads	5 W.T. - 1 non W.T.			
Number of water ballast tanks, and their capacity in tons	Six 737			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel	5915	Tons.	Ditto per inch immersion at same depth	28.5	Tons.
--	------	-------	--	------	-------

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. B. H. P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.	No. of Cylinders in each set.	
1	Triple Expansion	British	1942	Dominion Bridge Co. Ltd., Montreal, Que.	Three 20" 31" 55"	39"	-	146 N.H.P. 1176 I.H.P. 10-11 knots.
No. of shafts.	Particulars of Boilers.		When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. B. H. P. I. H. P. Speed of Ship.
	Description.	Number.			No. and Diameter of Cylinders in each set.	Length of Stroke.	No. of Cylinders in each set.	
2	Scotch	Two	1942	Dominion Bridge Co. Ltd., Montreal, Que.	55"			

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	2516.79	On account of space required for propelling power	915.67
Space or spaces between Decks	7.20	On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	
Fore or Trunk	9.29	These spaces are the following, viz. :-	
Forecastle	38.04	Coop.....82.26)	
Bridge space	86.39	Deck Houses.....115.54)	197.80
Coop or Break	41.37	(Number of Seamen or Apprentices for whom accommodation is certified.....)	
Side Houses	92.52	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :-	
Deck Houses	6.38		
Chart House			
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894	63.49		
Excess of Hatchways		Cubic Metres.	
Gross Tonnage	2861.47	Master's Accom.. 10.00)	
Deductions, as per Contra	1203.47	Chart Room..... 6.38)	90.00
Register Tonnage	1658.00	W.T. Room..... 8.31)	
		B'swain's Store 14.65)	
		Water Ballast 50.66)	
		Total ... 50.66)	

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 379.39 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 89.43 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Galley 9.09 tons - Wheelhouse 9.77 tons - Steering Gear 17.85 tons - Refrigerator 7.35 tons - Toilets 4.26 tons - Open Bridge Spaces 196.33 tons - Open Forecastle Spaces 43.40 tons - Light & Air 89.43 tons.

Name of Master	Certificate of	Service No.	No. Competency No.
Name, Residence, and Description of Managing Owner if there are more owners than one.			
His Majesty the King, in right of Canada, represented by the Honourable the Minister of Munitions and Supply of the Dominion of Canada, for the time being, Ottawa, Ont.			
Sixty-four (64) shares.			
Park Steamship Company, Limited, of Montreal, Que., designated MANAGERS.			
Signed at Montreal, Que., 29th January, 1943.			

