

Notes referring to the particulars on page 2 of this Certificate.

- (1) Stewards, Cooks, etc., attending on passengers, and Passengers' Servants are not part of the Crew for whom space is to be deducted, but spaces occupied by Stewards or Mess-room boys engaged exclusively in attending on the Master, Officers, Engineers or other Members of the Crew, may be deducted. The cabin occupied by the propelling machinery engineer's (but not the refrigeration engineer's) storekeeper may be deducted.

A dispensary for the exclusive use of the Crew may be deducted.

- (2) The accommodation for the Pilot, Purser, Clerk, etc., is not to be included in this deduction.
- (3) The deduction of Doctors' cabins is subject to the condition that they must be actually occupied by the Doctors.
- (4) The following spaces may be deducted:—A mess-room, if there is any, for the exclusive use of the officers; a second mess-room, if there is any, for the exclusive use of the engineers; and a third mess-room, if there is any, for the exclusive use of the petty officers.

No deduction is allowed for the officers' mess-room in ships having passenger accommodation, which are not also provided with a passengers' mess-room.

- (5) Where a one-berth cabin is provided solely for the accommodation of a pilot, the existence of such a room, although not itself eligible for deduction, shall not cause the disallowance of the officers' mess-room, bathroom, W.C., etc., as would be the case if the room were intended for the use of a passenger. Any passageway leading to the Pilot's room is not eligible for deduction.
- (6) The Captain's accommodation comprising rooms certified for his exclusive use may be deducted. Carriage of merchandise in the Captain's rooms will forfeit their deduction.
- (7) All spaces fitted as bathrooms, or lavatories, for the exclusive use of the Master, ship's officers, engineers, and crew, may be deducted, with the exception of such of the said bath rooms as are available for passengers when no bath room for their exclusive use is provided.
- (8) Deductions may be made for the spaces occupied by the laundry, refrigerating machinery, disinfecting and distilling apparatus provided that they are certified for the exclusive use of the crew and that the spaces containing them are solely occupied by them. Cold storage rooms shall not be considered as refrigerating machinery.
- (9) All spaces specially provided for the storage of search-lights, and for the wireless telegraphy installation may be deducted on condition that they are situated on the upper deck.

N.B.—The deduction of the spaces mentioned above is subject to the condition that they are clearly and permanently marked so as to show the purpose for which they are exclusively appropriated.

- (10) The deductions in the aggregate must not exceed five per cent. of the entire Gross Tonnage of the Ship, and so soon as any stores or cargo are carried in or passengers are berthed or accommodated in any of the spaces deducted the whole of the deduction in respect of the particular space will be permanently disallowed.