

Breadth 57.0

Do. Long Bridge to top of keels x

If surveyed while building, afloat, or

Depth 34.85

Draught Moulded feet. 26.83

Building in Builders drydock

FRAMES DOUBLE BOTTOM AND BEAMS.

Todd-Bath Iron Shipbuilding Corporation, Portland, Me. Yard No. 8

Sent to Chief Surveyors..... OAKBY Received from Chief Surveyors.....

VESSEL'S NAME s.s. "OCEAN PRIDE" Report N.Yk. No. 42656

For the CHIEF SHIP SURVEYOR and CHIEF ENGINEER SURVEYOR

(In cases which have to be submitted to the Classing Committee "the endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

Nature of Survey First Entry

This is a sister vessel to the "OCEAN LIBERTY" etc.

The scantlings are suitable for a draught of about 18½" in excess of that corresponding to the freeboard which could be assigned as a C.S.S. vessel.

100A1 "With freeboard"

2 Dks "Electrically welded"

Cell DB 368' 1310t, DTA 20' 734t, FPT 124t, APT 166t,

FK, 7BH (Coll to W dk, 6 to 2nd dk) 6 divisional W.T. BHs in 'tween dks., pt. Cem., Lloyd's A & CP

O.L. 441.5'

a+

E.S.D.

The class is assigned and maintained upon the understanding that the equipment will be made to accord with the requirements of the Rules when the present state of emergency has passed.

Insert in S.R.L.:- (A bower anchor and 45 fms. of chain cable to be supplied).

The Surveyors should be informed it is concluded the openings in the 'tween deck bulkheads have been closed in accordance with M.S. 1835 dated 21.3.40. A notation "6 divisional W.T. BHs in 'tween dks" is therefore being inserted in the Register Book.

FLOORS

Flat Plate Keel Angles

Side Keelsons, No. each side

Spacing

Fourth Deck, amidships, Angle, [or [.....

INCHES IN SHIP.

6 3½ .38

6 3½ .38

42/ .50

43½" X .54

1 @ .38

68 X .54

WELDED TO TAN SIDE BRACKET

12 X .44

TOLD

15 X .44

85.5 X .44

60 X .52

.44

YES

7 4 .38

✓ ✓ ✓

EVERY FRAME

8 4 .43

7 4 .38

EVERY FRAME

8 4 .50



© 2021



25.8.42

Lloyd's Register Foundation