

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name s.s. "ENNERDALE"

Official No. 168196

Port of Registry London.

This ship has been under survey at Cardiff

on 8th. March 1956 and the following alterations to the conditions of assignment of loadlines have now been effected/found:—

A new strongly constructed steel ventilator now fitted in forehold tween deck space on starboard side where a Diesel driven emergency fire pump has been installed.

Height of coaming above upper deck .36".

Thickness of coaming 5/16" — ? . 34

Diameter of coaming 12".

A permanent steel mushroom cowl fitted and canvas cover supplied.


Deck compensated in way of opening.

There is a strongly constructed steel escape door from the steering flat cut in the poop sheerstrake plating at the extreme after end of the vessel.

Size of orifice 18" x 18".


Size of door 21" x 22" x 1/4".

The door is operable from inside only and is fitted with a strongback and screwed steel dog.



N. S. S. S.
22.3.56.

A copy of this Report has been placed on board.



© 2021

Lloyd's Register
Foundation

010461-010465-0040