

(Settling Tanks)

See
enderson

Oil fuel may be carried in No's
2, 3, 4 & 7 Double bottom tanks
provided any holes in the centre plates
be efficiently closed, cofferdams be
arranged separating any fresh water
from the oil fuel and a complete ceiling
is fitted in bottom with at least $\frac{1}{2}$ air
space between the ceiling and the
inner bottom plating. The ceiling
may be omitted provided the seams of the
inner bottom plating be welded and the
seamships and condition of the plating & riveting
are found satisfactory.

Insulation
to be fitted on
the whole side
of Rinkhead
has top of tank
52 in accordance
with Sects 20
cl. 12 of the Rules
of Rinkhead
Sects 20
cl. 12 of the Rules

list of
H. B. Tanks

frame to be
fitted at
fitted for 509.

MARKS

Fuel oil tanks frames 52-59.

Bln 35.



© 2021

Lloyd's Register

Foundation 0104950272