

Rpt. 8

## REPORT OF SHIP SURVEYS AND REPAIRS

Received London

21 SEP. 1962

Ship's Name SS/MS "WEYBANK"

Gross tons 7367

Is there a rpt. 9? No

Port Melbourne

Rpt. No. 19804

No. of visits Three

First date 10-9-62

Last date 13-9-62

Interim Cert. issued  
& copy herewith? YesDamage rpt. issued  
& copy herewith? No

Last rpt. (H.Q. only) 8088 N.S.W.

Date of  
completing rpt. 17-9-62

Surveyed at, if different from Port above -

Surveyed afloat  
and/or in D.D. Afloat

Last date of examination in D.D.

Has a Lead Line

Survey been held? No

Freeboard Marks verified No

State which additional Rpt. 8 is attached: (Cont); (PS); (DR); (EQ); (Rig)

Survey fees £20 -0 -0

Damage fee -

Expenses £1 -4 -0

S.A. fee -

have surveyed the above ship in accordance with the Rules for

Hull Repairs.

The items now surveyed are detailed on this report. All were found or placed in good condition unless otherwise stated.

Repairs. (Wear & Tear)

Main deck plate abreast No.5 Hatch starboard side between frames 23 & 24 found fractured. Fracture approx. 9" long in line with forward edge of hatch aft corner underdeck doubling plate. Fracture now veed out and welded, examined under hose test and considered to be satisfactory. Aft Peak bulkhead plating fractured approx 1" along bottom edge of fifth stiffener to port from centreline. Fracture now veed out, and welded, examined with Aft Peak under pressure and considered to be satisfactory.



I recommend that this ship remain as classed ~~with~~ without fresh record of dry docking

subject to the conditions at present attached to the class of the vessel being dealt with as recommended.

(Where conditions of class are recommended to be retained, imposed, amended or deleted, particulars must be stated above and on the interim certificate)

Date of Committee WEDNESDAY 10 OCT 1962

Minute

Deferred for SS (by 12.62)  
(Subject)

A.L. Simpson.  
A.L. SIMPSON.  
Surveyor to Lloyd's Register of Shipping

ALSO FOR

SPL FOR

TRO

SRL

POSTING

HEADER

CERT

Lloyd's Register  
Foundation

010580-010588-0076