

*How "Registers"*

LOYD'S REGISTER  
LONDON.

OC  
ANSO

# Lloyd's Register of Shipping

BRITISH COLUMBIA

802-3 YORKSHIRE BUILDING

VANCOUVER, B. C., August 18, 1919

The Secretary,  
Lloyd's Register of shipping,  
71 Fenchurch Street,  
London . E. C.

Initial S.

Dear Sirs:—

We are in receipt of your letter dated 15th July in connection with report No. 742 "Canadian Volunteer"

In reply we wish to state that the centre girder bottom angles are .625 in vessel and not .525 as stated in report, and semi box beam of 3x3x.40 angle to bulkhead 24"x.38 plate and 6 x 3 $\frac{1}{2}$  x .40 bulb beam bracketed to stringer plate on port and starboard sides is fitted on fore side of collision bulkhead in way of second panting stringer, the collision bulkhead plating including floor plate is fitted as per approved plan and as herein stated, .40 floor plate, bulkhead plating .34 .32 .30 .28 & .26 at main deck.

WE trust same will be found in order

I am, Dear Sir

Yours faithfully,

*John Whitehead*



© 2021

Lloyd's Register  
Foundation

Referred to the Chief Ship Surveyor.

JRM.

SEP - 8 1916  
Also for Mr. S. A. Hill to note.

  
4 9.19



© 2021

Lloyd's Register  
Foundation