

F.E.

1500, 10, 40.

Sir James Laing &amp; Sons Ltd., Sunderland.

Yard No. 744

Received by Chief Ship Surveyor.....

Received from Chief Ship Surveyor.....

VESSEL'S NAME S.S. "EMPIRE THACKERAY" Rpt. Sld. No. 33477

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

1st Long. No. 7595

Depth "d" -

2nd Long. No. 21957

Proportions =  $\frac{L}{D}$  12.65

raming Bulb angle frames as approved Sheerstrake As approved

This is a sister vessel to the "EMPIRE WOLFE", "EMPIRE NEWCOMEN"  
and "EMPIRE DUNSTAN".

The tank top plating is increased under the hatchways in lieu of  
ceiling.

This vessel appears to have been built in accordance with the  
rules and the approved plans, and it is submitted she is eligible to  
be classed **100A1**

1 Dk

Cell DB 270' 627t, FPT 59t, APT 117t

FK, 5BH, Cem., Lloyd's A &amp; CP

P 33' B 82' F 34'

O.L. 328.2'

u



The class is assigned and maintained upon the understanding that the equipment will be  
made to accord with the requirements of the Rules when the present state of emergency  
has passed, and that cargo battens will be fitted at the first available opportunity.

Insert in S.R.L: (A bower anchor and 45 fms of chain cable to be supplied).  
Cargo battens to be fitted at the first opportunity.

With reference to the lengths of the erections as reported, the  
Surveyors should be referred to Circular No. 1551. It appears the correct  
lengths, for record in the Register Book are, as in the previous sister  
vessels "EMPIRE WOLFE", "EMPIRE NEWCOMEN", and "EMPIRE DUNSTAN", 33', 82'  
and 34'.



© 2021

Lloyd's Register  
Foundation

010727 010733 0160

Flat Plate Keel Angles

Side Keelsons, No. each side.....

Fourth Deck, amidships, Angle, [ ] or [ ] .....