

CROSSLEY BROTHERS LTD MANCHESTER, 11.
ENGLAND

Bruntons (Sudbury 1918) Ltd.,

3rd. June. 1947.

Sudbury,

20430.

SUFFOLK.

Openshaw Works

Authorised on Form M.

235/REM4/BULK.

Symbol. MET2D

Auth No. 39500.

Period. 3. 1947.

2 Sets :- Sterngear, each to transmit 165 B.H.P. at
300 R.P.M. (B.S.1. Rating) from a 4 cylinder,
2 cycle Marine Oil Engine and consisting of
the following:-

- One - Forged Ingot Mild Steel Tailshaft 5ft - $7\frac{1}{2}$ " overall
length, taper turned and keywayed for propeller
and with solid forged flange coupling at forward
end.
- One - Cast Iron Sterntube 5ft - $2\frac{1}{2}$ " long fitted with
gunmetal neck ring and cast iron stern bush,
fitted with "Vesta Neox" Gland.
- One - Forged Ingot Mild Steel Intermediate Shaft 5ft -
4" between flanges with forward flange to suit
engine thrust shaft flange.
- One - Totally enclosed, ring-oiling, whitmetal-lined
Plummer Block.
- One - Three-Bladed, Right Hand, Manganese Bronze Propeller
63 $\frac{1}{2}$ " Dia x 45" Pitch.

The above generally in accordance with your
quotation dated 2/5/47 and drawing No. 3/1888, but
shaft dia to be increased in accordance with our
letter 13/5/47.


TO LLOYD'S SURVEY REQUIREMENTS, TEST AND INSPECTION,
CERTIFICATE IS REQUIRED.

DELIVERY:- January 1948.

2214.

As above.

Att.

© 2021
Lloyd's Register
Foundation

