

# Lloyd's Register of Shipping.

## SURVEYS FOR FREEBOARD.


### (CONDITIONS OF ASSIGNMENT.)

 Index No. \_\_\_\_\_  
 (For London Office only).

GRK. REPORT NO. 21266.

Ship's Name "GAPE HAWKE" KALLIOPPort of Survey PORT GLASGOW.Official Number 168672Surveyor's Signature J. A. JamesonNationality and Port of Registry BRITISH. GLASGOW.Date of Survey WHILE BUILDING.

Disposition and dimensions of superstructures, trunks, deckhouses and machinery casings to be inserted in the diagrams and tabular statement:--



Particulars of Superstructures, Trunks, Casings, Deckhouses.

	Coaming	Plating	Stiffeners	Spacing	End Attachments of Stiffeners	Size of Openings	Height of Sills	Height of Casings
Poop Bulkhead ...	.30" ✓	.30" ✓	3 1/2" x 2 1/2" x .30"	30" x 37 1/2" ✓	NONE ✓	NONE ✓	✓	9' 0" ✓
Raised Quarter Deck Bulkhead ...	✓							✓
Bridge, After Bulkhead ...	.30" ✓	.30" ✓	3 1/2" x 2 1/2" x .30"	30" x 37 1/2" ✓	NONE ✓	2 @ 5' 0" x 4' 0"	18' ✓	9' 0" ✓
Bridge, Forward Bulkhead ...	✓							
Forecastle Bulkhead ...	✓							
Trunk, Aft ...	✓							
Trunk, Forward ...	✓							
Exposed Machinery Casings on Freeboard or Raised Quarter Decks ...	✓							
Exposed Machinery Casings on Superstructure Decks ...	.32" / .50"	.31"	3" x 3" x .30"	30" ✓	BKTS AT TOP ✓	5' 0" x 2' 0"	18"	8' 3"
Machinery Casings within Superstructures not fitted with Class I Closing Appliances ...	.50" ✓	.50"	3" x 3" x .30"	30" ✓	-DO- ✓	5' 0" x 2' 0"	18'	9' 0"
Deckhouses on Flush Deck Ships ...	✓							

Particulars of Closing Appliances (state if capable of being manipulated from both sides).

Poop Bulkhead ...	<del>NONE</del> openings
Raised Quarter Deck Bulkhead ...	✓
Bridge, After Bulkhead ...	SHIFTING BOARDS 3/4" THICK FULL HEIGHT IN CHANNELS RIVETED TO BULKHEAD. ✓
Bridge, Forward Bulkhead ...	✓
Forecastle Bulkhead ...	✓
Exposed Machinery Casings on Freeboard or Raised Quarter Decks ...	✓
Exposed Machinery Casings on Superstructure Decks ...	STEEL DOOR TO STROKEHOLD, WORKABLE FROM BOTH SIDES. ✓
Machinery Casings within Superstructures not fitted with Class I Closing Appliances ...	STEEL DOOR TO ENGINE ROOM, WORKABLE FROM BOTH SIDES. ✓
Deckhouses on Flush Deck Ships ...	✓







# PARTICULARS OF PROTECTION TO OPENINGS, ETC.

HATCHWAYS ON FREEBOARD AND SUPERSTRUCTURE DECKS.											
FREEBOARD DECK						SUPERSTRUCTURE DECK					
Description of Hatchway	No 1 CARGO.	No 2, 4 & 5 CARGO	No 3 CARGO.	No 3. W.T. PORT & STB SPACE	No 1. CARGO	No 2, 4 & 5 CARGO	No 3 CARGO	TONNAGE HATCH.	CARGO HATCH P&S.	CARGO HATCH P&S.	
Dimensions of Hatchway	31'-6" x 20'	31'-0" x 20'	10'-4" x 20'	7'-8" x 8'-6"	10'-5'-2"	31'-6" x 20'	31'-0" x 20'	20'-8" x 20'	5'-2" x 20'	10'-4" x 8'	
COAMINGS	<div> <div> Height above Deck Thickens Stiffeners Brackets, Stays </div> <div> Sides Ends </div> </div>										
HATCH BEAMS	<div> <div> Number Spacing Scantling and Sketch </div> <div> </div> </div>										
FORE AND AFTERS	<div> <div> Number Spacing Unsupported Lengths Scantling* and Sketch </div> <div> </div> </div>										
HATCH COVERS	<div> <div> Material Thickness How fitted Bearing Surface </div> <div> W.P. 2 1/2" F.A.A. 4" 3" AT ENDS. </div> </div>										
Spacing of Cleats	24"	24"	24"	BOLTS SPACED 24"	24"	24"	24"	24"	24"	24"	24"
Number of Tarpaulins	1	1	1	APART.	1	2	2	2	1	2	2
<p>*Are wood fore and afters steel shod at all bearing surfaces? YES.</p> <p>Are battens and wedges efficient and in good condition? YES.</p> <p>Are tarpaulins in good condition and in accordance with rule requirements? YES.</p> <p>Are lashings provided in accordance with rule requirements? YES.</p>											

Particulars of any special features:—

SMALL HATCHES ON FREEBOARD DECK.  
TRIMMING HATCHES.  
14 OFF 27" x 27", 4 OFF 29" x 24"  
COAMINGS 12" x 3 1/2" x 40" B.A. WITH 2 1/2" HINGED WOOD  
COVERS, CLEATS AND 1 TARPAULIN.  
SMALL HATCHES ON SUPERSTRUCTURE DECK. *Within forecabin*  
TO CHAIN LOCKER 2'-0" x 2'-6". TO FORE PEAK STORE 4'-0" x 3'-0"  
COAMINGS 9" x 3 1/2" x 40" B.A. 2 1/2" WOOD COVERS, CLEATS  
AND ONE TARPAULIN.

Endorsement at first survey and at surveys for renewal of Certificate:—

The fittings and appliances are in accordance with the particulars shown on this form (or as now modified) and are in good condition.



© 2021

Lloyd's Register  
Foundation