

384

S.N. REDRIVER

AND

S.N. REDFERN

Depth.

Similar to Redclond. ✓

Camber - No allowance as in  
- as Redclond. ✓Substructure.

Loop	S	E
	17.50'	17.0'

SL = .069 %

EL = .069 %

No allowance line A ✓

Sheers Credit can be given etc as for Redrivers

Ship. AL. 10.144  
 Pl. 10.44 ✓  
 18. 20.98 ✓  
 1.16 ✓

Stand. 17.375 ✓

Differnce. 16.195 ✓

Correction. 16.195  $\times$  .716 = 11.6 ✓ ONSummery. + Tabular freboard corrected for C<sub>a</sub> and Flush Deck.

Depth 5.07 ✓

Sheer 11.6 ✓

Surge -

Camber -

16.67 ✓

= 37.31 ✓  
~~40.21~~

+ 16.67 ✓

53.98 ✓

As the freboard is measured etc } + 10.05 ✓


64.03 ✓

To agree premium assignmt.

+ 3.97

68.00 ✓

Depth to freeboard Deck etc.

Deduction for Fresh Water  $d/4 = 3\frac{1}{2}$ 

corresponding

© 2021

freboard. 5'-4 1/2 ✓

Lloyd's Register  
Foundation