

(LLOYD'S REGISTER.)
VESSELS OF 100 TONS AND UPWARDS.

G.R. 130.
Lloyd's Register.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.
Signal Letters (if any) **L.B.N.T.**

Official Number.	Name of Ship.	No., Date, and Port of Registry.
160,404.	King Neptune.	91 in 1928 London.

No., Date, and Port of Previous Registry (if any).							
Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.			
British	Motor Ship Single Screw	Belfast	1928	Harland and Wolff Limited, Belfast.			
Number of Decks ...	One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...	Feet.	Tenths			
Number of Masts ...	Two				400	7	
Rigged ...	F & A Schooner				Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...	399	9.7
Stern ...	Cruiser				Main breadth to outside of plank ...	54	8.0
Build ...	Clencher				Depth in hold from tonnage deck to ceiling at midships ...	27	2.5
Galleries ...	----				Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...	--	--
Head ...	----				Depth from top of beam amidships to top of keel ...	30	7.5
Framework and description of vessel ...	Steel Cargo				Depth from top of deck at side amidships to bottom of keel ...	29	7.8
Number of Bulkheads ...	Seven				Round of beam ...	1	1.25
Number of water ballast tanks, and their capacity in tons	Nine 1452 Tons				Length of engine room, if any ...	49	--

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel	10808 Tons.	Ditto per inch immersion at same depth	44.8 Tons.
--	-------------	--	------------

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. B. H. P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.	No. of Cylinders in each set.	
One	Vertical Internal Combustion Four Stroke S.A. Diesel.	Engines. British	Engines. 1928	Engines. Harland and Wolff Six Limited, Belfast.				488
One	Vertical Type Oil fired	Boilers. British	Boilers. 1928	Boilers. Cochran & Co. (Annan) Limited Annan.	740 M/M	1500 M/M	----	1900 2350
								10 knots.

PARTICULARS OF TONNAGE.

GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.	
Under Tonnage Deck ...		4806.62	On account of space required for propelling power		1671.56	
Space or spaces between Decks...			On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew		233.41	
Turret or Trunk ...		22.97	These spaces are the following, viz.:—			
Forecastle ...			In Poop and Deck Houses			
Bridge space ...		81.10	(Number of seamen or apprentices for whom accomodation is certified) 35			
Poop or Deck ...		250.08	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—			
Side Houses ...			Masters Accommodation 12.57	} 182.25		
Deck Houses ...			Chart Space 7.29			
Chart House ...			Wireless House 4.56			
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...			Boatswains Stores 34.61			
Excess of Hatchways ...		62.87	Water Ballast Spaces F.P.T. 34.81			
Gross Tonnage ...		5223.64	" " Total ... A.P.T. 88.41		2087.22	
Deductions, as per Contra ...		2087.22				
Register Tonnage ...		3136.42				

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 681.72 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 153.31 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Forecastle	L.18.0'	-	46.81 Tons.
Open Bridge	L.141.2'	-	504.27 "

Name of Master	Certificate of Service No.	Competency No.
----------------	----------------------------	----------------

No. of Owners
Name, Residence, and Description of Managing Owner if there are more owners than one.

King Line Limited
65 London Wall,
London.
Shares Sixty four.

George Dodd of same address, Manager-

Dated 5th April, 1928.

