

Lloyd's Register of Shipping.

Ship's Name "RALLUS"

Official No. 147180

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

NOW DONE IN CONNECTION WITH OPENING UP OF SHELTER DECK

Tonnage opening in shelter deck restored and fitted with efficient temporary covers. ✓

Openings in tonnage well bulkheads now closed as required for full allowance. All scuppers previously led to the hold bilges from tonnage exempted shelter tween decks have now been closed by welded plates. Two scuppers have been fitted on each side of the vessel in the shelter tween deck and led to the machinery space bilges, the lower ends being fitted with weighted self closing cocks. ✓

Overboard scuppers 5" dia. have been fitted port and starboard abreast the tonnage hatch. These being automatic non-return valves controlled from the shelter deck with indicator showing whether open or closed. ✓

The coamings, covers, supports, bearing surfaces, tarpaulins, cleats and battening arrangements of all tween deck hatches are in order. New freeboard marks cut in and verified. ✓

The Gunners accommodation fitted in the shelter tween deck has been removed and all side scuttles and overboard connections in connection with this have been permanently blanked off. ✓

(Copy placed on board)

Closing Appliances Bridge } Bulkhead (Forward Bulkhead
Forecastle } tonnage well)

Hook-bolted steel plates.

A.R.
30.12.49

Poop Bulkhead (After bulkhead tonnage well)
Hook-bolted steel plates.

A.R.
30.12.49

E.J.
30 NOV 1946



© 2021

Lloyd's Register
Foundation