

56 JAN 1947

Index No.

Lloyd's Register of Shipping.

Ship's Name "SHELBURNE COUNTY"
(ex "Riverview Park")

Official No. 174158

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in LAUZON, P. Q., 1943.

Reference - Report C.11 (cont'd.) issued by the Surveyors, Saint John, N. B.,
dated 23rd February, 1946.

Ventilators on Upper Deck - All the additional Ventilator Coamings fitted on Upper
Deck have now been removed and plates fitted over the deck openings and welded.

Drainage - Openings on ship's side, draining Tween Deck, have been permanently closed
with plates fitted over openings and welded. The Valves on the ship's sides and
the extended spindles to the Upper Deck have been retained at the desire of the
Owners. The Tween Decks are now drained by scuppers fitted on the 2nd Deck
and led to bilges as formerly.

Tween Deck Bulkheads - Openings in Tween Deck Bulkheads previously arranged have now
been efficiently closed by plates fitted over these openings and welded.

Hatches - The previous arrangement for battening Tween Deck (2nd Deck) Cargo and Bunker
Hatchways and the additional fastening arrangements on Escape Hatches have not
been altered.

R. M. Scott

Surveyor to Lloyd's Register of Shipping,
HALIFAX, N.S.

4th December, 1946.

Noted ES

6 JAN 1947

Mr. Miller
to Note



© 2021

Lloyd's Register
Foundation

01140-01148-0067