

## FREEBOARD REPORT on the Tanker "OILFIELD".

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval. subject to:-

- (1) the companionway on the forecastle deck being fitted with a steel door which can be manipulated from both sides, the door sill being at least 24" in height.
- (2) the freeing ports being fitted with a horizontal rail or bar in accordance with Rule 35(c) of Statutory Rules and Orders 1932, No.96.
- (3) the exposed machinery casing on Poop deck being fitted with a steel door in accordance with Rule 97 of Statutory Rules and Orders 1932, No.96.



© 2021

011294-011303-0107

Lloyd's Register  
Foundation