

Lloyd's Register of Shipping.

Ship's Name "MARCHDALE" Official No. 174817

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in North Vancouver, B.C. - 1943.

The following modifications have been carried out at Saint John, N. B.:-

New messroom fitted in way of midship accommodation, starboard side forward, and formed by extending midship house side, galley front and boat deck over.

Two hinged steel W.T. doors fitted, one in side and one in front - doors manipulated from both sides - height of sill 18".

1 - 1 1/2" diam. discharge from sink in way of above led overboard and fitted with brass storm valve.

2 - 8" diam. cowl ventilators fitted on boat deck to above space, coaming 33" x 0.36", fitted with wood plugs and canvas covers.

Access hatch to strong room fitted in way of officers saloon - hatch 3'-6" x 2'-3" x 3 1/2" coaming, fitted with hinged steel lid.

4 - 24" diam. cowl ventilators (one each port and starboard at after end of No. 2 hold and forward end of No. 4 hold) now removed and deck plating efficiently closed.

4 new strongly constructed samson posts fitted (one each port and starboard at after end of No. 2 hold and forward end of No. 4 hold) and deck plating in way suitably stiffened.

Hold ventilation now arranged through samson posts, 18" diam. geared cowls being fitted to top of each post; original 24" hold ventilators at after end of No. 2 hold and forward end of No. 4 hold now removed and deck openings efficiently closed.

W. Neave
Surveyor.

Saint John, N. B. - May 28th, 1947.

(Copy of Rpt. C11 (Cont'd) has been placed on board the vessel)

Noted. F

3 JUN 1947

