

# Lloyd's Register of Shipping.

Ship's Name S.S. "DUNDURN PARK"Official No. 174817

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines  
in 6th December, 1943.

ALTERATIONS:-

Port Side:- D.E.M.S. Accommodation forward of No.19 bulkhead in  
in No.5 'tween deck now removed and bulkhead extended  
to ship's side with necessary stiffeners.  
Five ventilators (One 18" dia., one 12" dia. and three  
6" dia.) on upper deck, nine portlights and two storm  
valves in way removed and openings closed with welded  
spigot plates.

Starboard Side:- One room removed in No.5 'tween deck necessitating  
moving bulkhead aft three frame spaces. One 2'-0" dia.  
escape hatch on upper deck and two portlights in way  
removed and openings closed with welded spigot plates.

Forward Magazine:- In No.1 'tween deck removed together with access  
trunkway and hinged steel door. Deck aperture closed  
with welded plate. Upper deck girder extended and  
bracketted to collision bulkhead.

All new work satisfactorily hose tested on completion.

*D. J. Thibault*

SURVEYOR TO LLOYD'S REGISTER OF SHIPPING

Vancouver, B. C.

3rd December, 1945.

*ASD*  
*25/2/46*

