

Lloyd's Register of Shipping.

Ship's Name "ARABIA" ONSHUN

Official No. 182394

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Conversion of lower part of No. 1 Hold into a deep tank for the carriage of water ballast

The following additional ventilators have been fitted:-

Upper Deck. 2 @ 12" dia, coaming 4'6" x 34" bracketed 1 (p) & 1 (s) abreast fore mast.

Forecastle Deck. 1 @ 15" dia, coaming 3'0" x 36" fitted on centre line abaft windlass

Ventilators fitted with W.T. screw down steel tops, rubber jointed.

The following additional air pipes have been fitted.

Upper Deck. 2 @ 4" dia. G.N. height to underside of mouth 36" fitted abreast fore mast.

1 @ 5" dia. G.N. height to under side of mouth 24" fitted inside forecastle space.

Air pipes fitted with wood plugs and chains

Thos S. Duffell

Surveyor to Lloyd's Register.

LIVERPOOL 14.9.49.

Noted
23 SEP 1949