

Lloyd's Register of Shipping.

30 DEC 1949

Ship's Name "EASTERN" Official No. 180145

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in 1944.

ALTERATIONS : NOW DONE : -

Six air change pipes to refrigerated spaces in No.5 upper tween deck fitted to freeboard deck aft, 3" dia., openings 30" above deck, with steel screwdown W.T. mushroom covers at openings.

One exhaust gooseneck ventilator from refrigerating machinery space, starboard side abreast midship deckhouse fitted to freeboard deck, opening 20" x 9", 14" above deck, coaming 1/2" thick, with a steel hinging W.T. cover at opening.

One inlet ventilator to refrigerating machinery space, starboard side abreast midship deckhouse, fitted to freeboard deck, coaming 20" dia. x 1/2" thick, 3' 9" high efficiently stayed.

Surveyor to Lloyd's Register

HONG KONG.

25th. October, 1949.

af



© 2021

Lloyd's Register Foundation