

"ROYAL IRIS"

Equipment Numeral.

L (B + D)		
157 (48 + 13.33)	=	9628.8
Houses Main Deck	$\frac{130 \times 7.75}{2}$	= 503.7
Shelter Deck	$\frac{130 \times 9.25}{2}$	= 601.3
Sun Deck	$\frac{26.5 \times 7.5}{2}$	= <u>198.7</u>
		<u>10,932.5</u>

£

9000	165
11000	<u>210</u>
	<u>45</u>

$\frac{45}{2000} \times 1932.5$	=	43.48
		<u>165</u>
	£	<u>208.48</u>

No. of visits 57

Fee £ 208.



©2021

Lloyd's Register  
Foundation

611636-011645-0222