

**(LLOYD'S REGISTER.)****VESSELS OF 100 TONS AND UPWARDS.**

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.

Signal Letters (if any)

Official Number.		Name of Ship		No., Date, and Port of Registry.	
183806		ROYAL IRIS		10 in 1951 - Liverpool	
No., Date, and Port of previous Registry (if any).			New Vessel		
Whether British or Foreign Built.	Whether a Sailing, Steam or Motor Ship. If Steam or Motor Ship, how propelled.	Where Built.	When Built.	Name and Address of Builders.	
British	Diesel Electric Twin Screw	Dumbarton	1951	William Denny & Bros. Ltd., Leven Shipyard, Dumbarton	
Number of Decks	One	Length from fore part of stem to the <sup>fore</sup> aft side of the head of the <del>stem</del> rudder stock		Feet.	Tenths.
Number of Masts	One Pole Mast	Main breadth to outside of <del>plank</del> <sup>plating</sup> floors		149	9.0
Rigged	Not rigged	Depth in hold from tonnage deck to ceiling amidships		48	1.0
Stem	Straight	Depth in hold from upper deck to ceiling amidships, in the case of three decks and upwards		12	3.5
Stern	Cruiser	Depth from top of deck at side amidships to bottom of keel		-	-
Build	Out and in	Round of beam		-	7.5
Framework and description of vessel	Steel Passenger Ferry	Length of engine room, if any		71	9.0
Number of Bulkheads	5 Complete 1 Partial				

Particulars of propelling Engines, etc. (if any), and Water Ballast Tanks, as supplied by Builders, Owners, or Engine Makers.

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. B. H. P. Estimated Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
Four	Internal Combustion and Electrical Transmission	British	1951	Ruston Hornsby Lincoln Metropolitan Vickers, Manchester	Six 10 $\frac{1}{4}$ "	14 $\frac{1}{2}$ "		97 540 each shaft
No. of Shafts. Two	Particulars of Boilers. Description Number Iron or Steel Loaded pressure	Boilers.	Boilers.	Boilers.				12 knots

Number of Water Ballast Tanks, and their capacity in tons:— Five - 131 tons

011636-011645-0223

[P. T. O.]

PARTICULARS OF TONNAGE.

GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.
Under Tonnage Deck ... ..		<u>611.04</u>		On account of space required for propelling power ...	495.16
Space or spaces between Decks ... ..				On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from Goods or Stores of every kind, not being the personal property of the Crew ... ..	53.43
Turret or Trunk ... ..		324.53		These spaces are the following, viz. :—	
Forecastle ... ..				<b>Below deck and Round House</b>	
Bridge space ... ..				(Number of Seamen or Apprentices for whom accommodation is certified ..... 3 .....	
Poop or Break ... ..				Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Side Houses ... ..		281.88			
Deck Houses ... ..					
Chart House ... ..		16.58			
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894					
Excess of Hatchways ... ..					
			Cubic Metres.	Master's Accommodation	6.05
Gross Tonnage ... ..		<u>1234.03</u>	3492.30	Chart Space .....	6.92
Deductions, as per Contra ... ..		611.75	1731.25	Steering Gear .....	24.60
Register Tonnage ... ..		<u>622.28</u>	1761.05	Water Ballast Spaces ::	25.59
				Total ... ..	63.16
					<u>611.75</u>

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 266.37 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 17.28 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage:—

Shelter Space Aft of Bar Length 10.0', 6.0', 2 0', 6.0', 4.1' = 58.82 tons  
 Ladies' Rest Room & Lavatory Length .5, 14.5' = 23.95 tons  
 Gents' Lavatory Length .5', 14.5' = 9.64 tons

Name of Master \_\_\_\_\_

No. of Owners \_\_\_\_\_ Certificate of { Service No. \_\_\_\_\_  
 { Competency No. \_\_\_\_\_

Name, Residence, and Description of Managing Owner if there are more owners than one.  
**The Mayor, Aldermen and Burgesses of the County**  
**Borough of Wallasey,**  
**Town Hall,**  
**Wallasey, Chester.**

Sixty-four Shares  
 Loyd Dearn Price, Manager  
 Wallasey Corporation  
 Ferris,  
 Seacombe Ferry,  
 Wallasey.

Dated 20th April, 1951

\* (13569)—W348/230/688—2M—7/50. P.P. 654



Lloyd's Register  
 Foundation