


# LLOYD'S REGISTER OF SHIPPING



Port

BIRMINGHAM

24th August, 1962.

Aalborg Vaerft A/S on. 2861/458 on  
Stewarts and Lloyds Ltd. W/O. 87409.

*Down tubes*

This is to Certify that

H. J. FELLOWS

the undersigned Surveyor to this Society did at the request of  
Messrs. Stewarts and Lloyds Ltd., attend at their Bromford Works,  
on the 13th and 17th July, 1962 for the purpose of inspecting  
and testing tubes to the order of Aalborg Vaerft A/S.

35 - 7.1/2" o.d. x 5wg. thk. x 16/20ft. = 678'10"  
318mm 8mm 5/6metres

9 - 12.1/2" o.d. x 5/16" thk. x 16/20ft. = 175'2"  
Hot finished seamless steel tubes, have been examined

internally and externally, gauged and all found satisfactory  
and in accordance with the terms of the order.  
The ends of the tubes were not ground.

The material from which the tubes were manufactured  
was made at an approved steel works and material tests  
were carried out on the finished tubes with satisfactory  
results in accordance with DIN 17175, Grade 1, matl.,  
St.35.8 and terms of the order.

All tubes have been hydraulically tested by the  
manufacturers to 1140 p.s.i. and 10% of these tests  
were witnessed by the Surveyor with satisfactory  
results. The manufacturers' certificate of 100%  
hydraulic test was accepted.

For the purpose of identification the tubes  
were stamped near one end:- HF.

Fee:- £6. 1s. 0d.  
Exam:- 7s. 6d.

*H. J. Fellows*

Surveyor to Lloyd's Register of Shipping.

This certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-  
The Council of the Society use their best endeavours to ensure that the functions of the Society are properly  
performed and it is to be understood that neither the Society nor any Member of any of its Committees in under any circumstances  
shall be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any  
Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of  
its Surveyors or any Member thereof, or the Surveyors, or other Officers or Agents of the Society.