

Lloyd's Register of Shipping.

4 MAY 1943

Ship's Name s.s. "OCEAN STRANGER". Official No. 87979

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in _____

Additional accommodation now provided in the No.4 and 5 'tween decks.

Access to No.4 'tween deck through a strongly constructed steel companion (p.s). aft. of machinery casing, opening 2'0" x 4'9" closed by wood door, sill 24".

Ventilators fitted have coamings 36" high, and are closed by wood plugs and canvas covers.

All sidelights fitted have hinged steel deadlights.

Sanitary discharges two Port and three Starboard fitted with S.D.N.R. valves controlled from the shelter deck.


The opening in the after bulkhead of the tonnage well closed by welded steel plate, and access to No.5 'tween deck space is through a companionway already fitted on the plate closing the well, and through the forward bulkhead of the well.

F.N. Sutcliffe

Surveyor to Lloyd's Register of Shipping,

Middlesbrough. 3.5.43.

W



© 2020

Lloyd's Register Foundation