

28 MAY 1959

Rpt. C. 11 (Contd.)

Index No. (For London Office use)

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

ADN. No. 2716

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name "SEIYUN" Official No. 169200

Port of Registry ADEN

This ship has been under survey at ADEN

on 8th January, 1959 and subsequently ¹⁹⁵⁹ and the following alterations to the conditions of assignment of loadlines have now been effected/~~1959~~:-

Hatchway coamings on the main deck numbers one and two hatches increased in height from nine inches to twenty four inches. Hatchway coaming plate thickness at sides and ends half inch. Horizontal half inch bulb plate stiffeners fitted to the hatch coamings and suitably supported at cantilevers with bulb plate brackets. The hatch beams and carriers and the hatchway cleats fitted as originals. The hatchway locking bars modified to be secured under the horizontal stiffeners.

Two small hatchways to the fore peak store space and transome space, coamings increased in height from eighteen inches to twenty four inches.

The door sills to the machinery space and accomodation space at starboard side increased in height to twenty four inches. The doors modified to suit the increased sill height.

Freeboard markings from the top of the steel upper deck at sides to the centre of the disc is eight feet and one half inch (8' - 0 1/2")

W. P. Watson

Surveyor to Lloyd's Register.

A copy of this Report has been placed on board.



© 2021

Lloyd's Register Foundation

011864-011876-0177

Noted
19/6/59