

10 OCT 1947

Index No.

38837

Lloyd's Register of Shipping.

Ship's Name "HAI SHUI" (ex "Haisu", ex Ottawa Paget*) Official No. _____

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in _____

Alterations:

Upon examination found forecastle space closed in for Crews' accommodation at previous date, steel casing being fitted athwartships between lamp room on port side to paint store on starboard side.

Steel plating 1/4" thick, 14 ft. 6 ins. in length, fitted at aft end of forecastle having one steel hinged door 36" x 58 1/2" capable of being opened from both sides. Sill 15". Casing securely fastened by riveting top and bottom. Stiffeners 2 1/2" x 2 1/2" x 3/8" are fitted 16 1/2" - 27" apart.

The lamp room and paint store have now been transformed into single berth cabins for crew.

Portlights: Three in number 12" dia. portlights with C.I. deadlights have been fitted to Crews' accommodation in forecastle both P. & S.

Small hatchways to Fore Peak Stores and Chain Locker remain unaltered.

Noted.

10 OCT 1947

BAK

Ritchie

