

19 NOV 1965

SHIP'S NAME "FREDRIKA"

PORT HAM

No. 15012

APPD. .... NIL

LAST SURVEY DATE 10.9.65.

CLASS IS SUBJECT TO NIL

Docking W/D 4.5 m/m rewooded to 7.0 m/m.  
TS(CL) due 5.65 new held.

Tailshaft drawn & found cracked in 3 places at top of the keyway (35-75 m/m in length & up to 1 1/2 m/m deep) cracks now ground out & placed on board. Survey recommends shaft be examined after 2 years when fitted. ~~but submitted this being reduced to 12 months~~  
A spare unused shaft in accordance with C1102 now fitted. Owners request 4 yr survey, but it is submitted in view of cracks now found in shaft removed 4 yrly surveys be withheld for the present.

It is submitted that this vessel is eligible to remain as CLASSED. TS(CL) N 9.65 new

18.11.65

4 year items as per Cable to Ham 3/8.65.

Appdx Note

Spare TS cracks ground out, to be specially examined 12 mos after being placed in service.



