

7 JUN 1943

Lloyd's Register of Shipping.

EVER FORTUNEShip's Name ~~Ex~~ "Empire Deed"

2047

Official No. ~~119113~~

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in 1943 - 5

Two steel companion have been fitted on
Upper deck aft each 6'-6" high 5'-3" long 3'-6" wide
with hinged wooden doors 1 $\frac{1}{2}$ " thick swinging
from either side. Sills 2 $\frac{1}{2}$ " high.

Additional ventilators have been fitted as
follows :-

Upper deck aft.	3 @ 12" dia	36" high	.34 thick.
"	1 @ 9"	" 36" "	.32 "
"	11 @ 6"	" 36" "	.30 "

The ventilators are closed by wooden plugs &
Canvas covers.

One 8 $\frac{1}{2}$ " dia ventilator on upper deck aft has
been removed.

In after tween deck additional discharges overboard
have been fitted 3 @ 4" dia, 1 @ 2" dia, each
fitted with storm valve at shell and control rod
to upper deck.

Jas Remond

31/5/43

Copies of the above placed on board.

Jas Remond

7 JUN 1943