

Nº 8-43/61.-

s.s. "CONSTITUCION".

Registry: Mexican.

Tonnage: 7066 gross tons.

Moored at North side of Pier Nº4.

Veracruz, ver. M E X I C O.-

At the request of Messrs. WATSON, PHILLIPS & CIA.,
SUGS., S.A., Lloyd's Agents for the district of Veracruz, the
under signed ROBERT DOBBIE, did proceed on board above men--
tioned vessel on the 1st day of December 1961, to inspect --
stbd. boiler according to instructions and reports as follows:

STBD. MAIN BOILER, SCOTCH, THREE FURNACES,
FOUND OPENED UP AND FOUND CLEAN ON WATER
AND FIRE SIDE.

FURNACES AND CROWNS WERE SCALED ON WATER
SIDE AND TUBES CLEANED OUT AND BOILER
MOUNTINGS: STOPS, SAFETIES, FEED CHECKS
AND OTHER VALVES OPENED UP GROUND IN AND
PLACED WITH NEW PACKING. BOILER WAS TESTED
TO 230 LBS. HYDRAULIC PRESSURE ON THE 3RD OF
DEC. AND SAFETY VALVES SET BY SHIPS ENGINEERS
WAS SEEN TO RELIEVE ON THE 5TH OF DEC. AT
220 LBS.

=====

This Certificate is issued without prejudice and
subject to the terms, conditions and amount of the Insurance
Policy.

Issued in Original and copies, one of which being
accomplished the others to stand null and void.

Copy of Original

Veracruz, ver. December 5th, 1961.

Robert Dobbie

Robert Dobbie.
(surveyor)



© 2021

Lloyd's Register
Foundation

012221-012228-0048