

COPY

LLOYD'S REGISTER OF SHIPPING



Port

BIRMINGHAM

Messrs. T. France, Amsterdam.
Order No. CV. 2063 on The
Coventry Victor & Motor Co. Ltd.

9th July 1964

*Engine supplied against
ref. 0.23058.*

This is to Certify that

H. BAILEY

the undersigned Surveyor to this Society did at the request of

The Coventry Victor Motor Co. Ltd., attend at their Coventry Works
on the 8th June and 2nd July 1964 for the purpose of inspecting and testing
the undersigned engine made to the order of T. France Amsterdam under order
No. CV. 2063.

NE - Type AD2 Aircooled Diesel Engine.

The engine is of the single cylinder, four stroke cycle, air cooled
type, fitted with constant speed governor with 85 m.m. bore cylinder 100 m.m.
stroke and designed to develop 5.5 HP at 1500 RPM.

This engine drives a Broon & Wade compressor through Vee belts,
and mounted side by side on a fabricated base.

Material tests from the crankshaft and connecting rod were carried
out by a Surveyor to this Society with satisfactory results.

The engine was coupled to a water brake and run on full load trials,
and cold starting, governing and running conditions were considered
satisfactory.

On completion of trials the engine was partially dismantled,
the moving parts examined and found satisfactory.

For identification purposes, the crankcase was stamped:-

CC6983 ENG 6642 LLOYDS REG 2/7/64 HB

H Bailey

SURVEYORS TO LLOYD'S REGISTER OF SHIPPING

Recd: 27-10-64.

Exp: 21-5-66.

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-

"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly
executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances
whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any
entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of
its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."