

37510

Lloyd's Register of Shipping.

11 OCT 1950

Ship's Name

"GEOLOGIST"

Official No.

168875

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in 1944.

Additional airpipes fitted due to conversion to oil fuel.
Main Deck. (After well).

No. 6. O.B. Tank (F.W.) - 4" dia. airpipes P.S. - 36" above deck.

" 7 " " (W.B.) - 2 3/4" " " " - 36" " "

Closing arrangements for above - wood plugs & canvas covers.

Bridge Deck.

No. 2 O.B. Tank (W.B.) - 2 1/2" dia airpipes P.S. - 36" above deck

" 5 " " (F.W.) - 4" " " " - 36" " "

Closing arrangements for above - wood plugs & canvas covers.

No. 3 O.B. Tank (O.F.) - 4" airpipes P.S. - 36" above deck.

Deep bunker (O.F.) P.S. - 4" " " - 36" " "

" " " Centre - 2-1/4" " " - 36" " "

Side bunker (O.F.) P.S. - 4" " " - 36" " "

Settling tank (O.F.) P.S. - 4" " " - 36" " "

Closing arrangements for above - wire gauge & canvas covers.

H. K. K. K. K. K. K.
B. K. K. K. K. K. K.
12.9.50.

Copy of above attached to ship's copy of Report C.11 and placed on board.

G.H.W.

117 OCT 1950