

Received London  
14 JAN 1965

Ship's Name ~~MS~~ "OSBORNE CASTLE" LR.526590.

Gross tons 736. Port of Registry Southampton. Port Southampton.

Date of build 3.62 Is there a Rpt. 9? No. Rpt. No. 29332.

No. of visits 2. First date 9/11/64. Last date 9/11/64.  
Interim Cert. issued & copy herewith? Yes.. Damage rpt. issued & copy herewith? No. Last rpt. (H.Q. only) See 29213.

Date of completing rpt. 11/1/65. Surveyed at, if different from Port above -

Surveyed afloat and/or in D.D. Afloat. Last date of examination in D.D. -

Has a Load Line Survey been held? - Summer freeboard as verified -

State which additional Rpt. 8 is attached: (Cont); (PS); (DR); (EQ); (Rig) -

Survey fees £7..7..0. Damage fee - Expenses 6/-

S.A. fee

18 JAN 1965

pr

I have surveyed the above-named ship in accordance with the Rules for Damage stated caused by contact with M.Y. "Shemara" after undocking 3-11-64.

Repairs Now Done:-

Starboard side:

Shell plate H 3 cropped and part renewed about 6' x 4', adjacent plate J 3 faired in place.

3 frames in way cropped, faired and refitted. Stairway recess plate cropped and part renewed.

Shell plate F 5 released and faired in place. 3 frames cropped, faired and refitted.

All repairs hose tested on completion and found tight.

The items now surveyed are detailed on this report. All were found or placed in good condition unless otherwise stated. I recommend, therefore, that this ship remain as classed ~~with~~ without record of dry docking.

(Where conditions of class are recommended to be retained, imposed, amended or deleted, particulars must be stated above and on the interim certificate.)

Date of Committee

MONDAY 25 JAN 1965

Minute

As above



Lloyd's Register Foundation

012694-012698-0060

ALSO FOR
SPL FOR
TRO
SRL
POSTING
HEADER
CERT

action taken or recommended should be described fully under "defects & repairs". When any part has been subjected to pressure test this should be stated.

date of the next Special Survey. Where repairs have been effected or it is considered that re-examination or repairs should be made before that date the circumstances and

The condition of any item is to be described as "good" only when it has been examined, found or placed in good condition and is considered to be acceptable until the due

PARTICULARS OF DEFECTS, REPAIRS, ALTERATIONS, ETC. The reason for repairs must be stated and repairs on account of damage, the alleged cause of which must be given, should be detailed separately from wear and tear repairs and, besides being detailed above, should be noted in the following summary. *State what action has been taken regarding items which are subjects of class or in SRL Appendix, whether outstanding or new.* Any alterations in existing particulars in the Register Book should also be reported above.

SUMMARY OF DAMAGE REPAIRS	SHELL PLATES	FRAMES	DECK PLATES	BEAMS	OTHER ITEMS
Renewed <b>part</b>	1	-			
Removed and faired or replaced		6			
Faired or repaired in place	1	-			



© 2021

Lloyd's Register  
Foundation