

# LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

F-3974

Ship's Name "LANTAO"

Official No. 167801

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in Kobe, September, 1956.

1. 49 damaged Simplex hatch covers on Nos.1 and 5 Upper deck hatchways and on Nos.2,3 and 4 Bridge ~~dk~~ hatchways replaced with 49 wood hatch covers. *provided with steel galvanized end bands.*

2. Two W.C.'s, one port and one starboard, of steel and of substantial construction, fitted on upper deck against Poop front bulkhead, inboard of the ships side, P.& S.

Ventilation: One 6" dia. M.V., 22" coaming, to each W.C.

Sanitary discharge: 3" dia., discharge from each W.C. led overboard below freeboard deck, with N.R.V. at ship's side.

2" dia. scupper from each W.C. led overboard below freeboard deck, with N.R.V. at ship's side.

*Wm G. McCulloch.*

Surveyor to Lloyd's Register of Shipping.

KOBE: 4th October, 1956.

*Notes  
pub  
29/10/56*

