

15 DEC 1945

Index No.

Lloyd's Register of Shipping.

BONNA

Ship's Name

S.S. "SALT LAKE PARK"

WARRUNA

Official No.

175392

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in May, 1944.

Alterations:-

Port Side:- D.E.M.S. accommodation forward of No. 19 bulkhead in No. 5

tween deck removed together with five ventilators (one-20" dia., one-12" dia., and three-6" dia.) on upper deck, nine port lights and two storm valves in way. Openings efficiently closed with welded spigot plates. Bulkhead extended to ship's side with required stiffeners.

Starboard Side:- One room removed necessitating moving bulkhead aft four frame spaces. One 2'-0" dia. escape hatch on upper deck and two port lights in way removed and openings closed with welded spigot plates.

Forward Magazine in No. 1 tween deck removed together with access trunkway and hinged steel door. Two-10" dia. ventilators removed and deck apertures efficiently closed with welded plates. Fore and aft girder extended to collision bulkhead with bulb angle stiffening.

All new work satisfactorily hose tested on completion.

D. J. Ambled

Surveyor to Lloyd's Register

Vancouver, B.C.

9th November, 1945.

AL
1812-45



© 2021

Lloyd's Register
Foundation

012 722-01222-0247