

# LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

Ship's Name

S. S. ~~"WAIKONA"~~**BONNA**

Official No.

~~175392~~

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in 1944

ALTERATIONS TO AFTER CREW'S ACCOMMODATION ON SHELTER DECK:-

1. After steel companion access to crew's accommodation situated at centre line at Frames 18 to 19 now removed and aperture in deck permanently plated over. ✓
2. Stairway from upper deck to 2nd deck (Frames 11 to 13) now removed and aperture in deck permanently closed with welded plate and new aperture cut in deck for stairway to port of centre line between frames 6 and 8 inside casing. ✓
3. Two additional steel skylights with steel hinged W. T. lids fitted one on Starboard side and one on Port side between forward end of accommodation casing and after end of No. 5 hatch coaming (each 2'-0" x 1'-6"). ✓
4. Two disused scuppers removed from frame spaces 18-19 and 19-20 starboard side. ✓
5. One 10" sidelight on starboard side removed from frame space 19-20, and refitted in frame space 21-22.

One sidelight on starboard side removed from frame space 10-11 and refitted in frame space 11-12.


2 - New 12" sidelights fitted on starboard side in frame spaces 30-31 and frame spaces 26-27 (with efficient deadlights).

2 - New 12" sidelights fitted on port side in frame spaces 26-27 and frame space 22-23 (with efficient deadlights). ✓


6. 1 - New storm valve fitted in frame space 24-25.

7. All disused apertures in shell plating closed with welded spigot plates. ✓

8. Upper deck over crew's accommodation, wood sheathing 5" x 2-1/2" edge grain fir lain and caulked and payed frames 4-34 port to starboard. Margin bars flat 2-1/2" x 1/2" edge welded to deck in way of waterways. ✓

  
For R. CHALCRAFT  
SURVEYOR TO LLOYD'S REGISTER.  
VANCOUVER, B. C.

3RD DECEMBER, 1952.

  
8 JAN 1953

